If these sums are not claimed within three months from the date of publication of this notice by the claimants or their legal heirs, the amounts will be credited to Government.

No.	Rank	Names	Amount
			Rs. a. p.
1. A. 124	Sepoy	Venkatrao	2 0 0
2. B. 189	Do	Subbiah	33 11 0
3. T. C. 707	Do	A. C. Anthony	1 14 0
4. T. C. 743	Do	Krishna	2 0 0
		Total	39 9 0
		(Rupees Thirty-nine and annas nine only.)	

G. MALLIKARJUNIAH,
For *Chief Commandant.*

GOVERNMENT OF MYSORE, ELECTRICAL DEPARTMENT.

OFFICE OF THE CHIEF ELECTRICAL ENGINEER IN MYSORE, BANGALORE.

Abstract Notification dated 29th July 1938.

SALE OF SECONDHAND STEEL POLES AT C. P. S. CENTRAL STORES.

Attention is drawn to this office Notification No. G. N. 26, dated 29th July 1938, inviting tenders for the above work, published in Part VI, Pages 1306 and 1307 of the *Mysore Gazette*, dated 4th August 1938. The last date for receiving tenders is 5th September 1938 and the earnest money required is Rs. 100.

Abstract Notification dated 29th July 1938.

SUPPLY OF HARDWARE AND ELECTRICAL MATERIALS TO M.P.L. SECTION.

Attention is drawn to this office Notification No. G. N. 27, dated 29th July 1938, inviting tenders for the above work, published in Part VI, Page 1307 of the *Mysore Gazette*, dated 4th August 1938. The last date for receiving tenders is 20th August 1938, 12 NOON.

A. C. MUNIRATNAM,
For *Chief Electrical Engineer.*

OFFICE OF THE SUPERINTENDENT, POWER AND LIGHT, MYSORE.

Notification dated 9th August 1938.

1. Sealed tenders in triplicate will be received at the office of the Superintendent, Power and Lighting, Mysore, superscribed with the name of the work mentioned below.

2. The plans connected with the work may be seen at the Office of the undersigned at all working hours. The copy, if required, will be made available on payment of Rs. 2 per set.

3. The tenders should be drawn up strictly in conformity with the specifications furnished, writing out the rates at which each item of work will be executed in figures as well as in words failing which no cognisance will be taken of the tender. No items other than those noted in the statement should be included as the items cover provision for all sundries, repairs to damaged masonry and painting.

4. The materials to be used on the work should be of best quality conforming to the specification of this department and B. S. or A. I. E. E. specification. Mention should also be made of the manufacture and the catalogue numbers of the materials offered. Teak wood planks to be used on the work should be free from cracks, knots and well seasoned. No planks less than 12" in width will be permitted to be used unless it is to make up the difference in size of the board required. Only the lap joints should be adopted in all cases.

5. The undersigned reserves the right to reject the tenders without assigning any reasons therefor.

6. The successful tenderer will be required to deposit an earnest money of Rs. 60 (Rupees sixty only) and execute an agreement within a week from the date of intimation of acceptance of the tender. He should send samples of all the materials required for the work mounted on a board and start the work after obtaining the approval of the undersigned with regard to the same and carry out the wiring following the rules of this department as well as that of the Institution of Electrical Engineers. He should also be prepared to adopt any change in the location of control points and other outlets that might be suggested by the undersigned during the progress of the work without extra cost if the tender is not materially affected by such deviations.

7. The undersigned reserves the right also to reject the work either in full or in part if he finds the work not carried out in terms of the specifications or is otherwise dissatisfied with the workmanship.

8. *Name of work.*—Installing electric lights and heating circuits to the New Out-Patient Dispensary attached to New Cheluvamba Maternity Hospital, Mysore.

9. *Last date for receiving tenders.*—29th August 1938, 3 P.M.

10. *Date and time of opening the tenders in public.*—29th August 1938, 4 P.M.

11. A period of four weeks will be allowed for final completion of the work with effect from the date of final acceptance of the tender. A penalty of rupees ten for each day's delay over and above the stipulated period during the first week and rupees twenty during the second week will be imposed. If there be further delay, the Department will take charge of the installation at whatever stage it might be and arrange for its completion through any other agency entirely at the risk of the tenderer.

12. It will be obligatory on the part of the tenderer executing the work to rectify any major defects that might occur during the first 12 months from the date of handing over the installation to this Department, without any return for services rendered.

13. *Details of work.*—The quantities given in the following statement are not guaranteed and are subject to variation at the time of executing the work.

Part I—Lighting.

1.	Supplying and laying No. 7/.044 SWG twin conductor paper insulated lead covered double steel tape armoured jute served underground cable in a trench 3 ft. deep and surrounding the same with 3" of fine sand, enclosing the ends of the cable in in-door and out-door type C. I. junction boxes, fitted with insulating compound, using 18 ft. of 1½" galvd. pipe for enclosing the cable at the pole, No. 7/.044 SWG insulated wire and accessories	110 R.ft.
2.	Supplying and running mains in ¾" heavy gauge braized conduit embedded in the wall using No. 7/.044 SWG insulated wire and accessories	8 R.ft.
3.	Supplying, fixing and wiring T. W. distribution board 3'×2'×1' with battens and rear board, equipping the same with a three-way iron clad distribution box D. P. H. O. pattern 10 amp. per way, with 10 amp. S. P. circuit switches bakelite, one D. P. S. T. 30 amp. iron clad switch enclosing the complete equipment in an iron box made up of ⅛" sheet iron mounted in a niche cut open in the wall provided with panelled shutter, lock and key, using No. 7/.044 and 7/.029 SWG insulated wires and accessories	No. One
4.	Do do in ¾" braized heavy gauge conduit with rectangular flush 'T' junction boxes, bends, etc. embedded flush with the wall for lighting outlets, using one 5 amp. flush type control switch with cream bakelite plate, ring, etc., using No. 7/.029 and 3/.029 SWG insulated wires for mains and taps respectively and accessories	11
5.	Do do for 5 amp. flush type wall plugs complete, with 5 amp. flush type control switch, cream bakelite plate, etc., as per above specification	3
6.	Earthing	Item

Part II—Heating.

1.	Supplying and laying No. 7/.064 SWG. twin conductor paper insulated lead covered double steel tape armoured jute serve underground cable in a trench 3 ft. deep and surrounding the same with 3" of fine sand, enclosing the ends of the cable in C. I. in-door and pole type junction boxes filled with insulating compound using 18 ft. 2" galvanised pipe for enclosing the cable at the pole and No. 7/.064 SWG insulated wire and accessories	110 R.ft.
2.	Supplying and running mains in 1¼" braized conduit embedded flush with the wall, using No. 7/.064 SWG insulated wire and accessories	8 R.ft.
3.	Supplying, fixing and wiring 4 (four) iron clad service cut outs 30 amps. and one D. P. S. T. 60 amps. iron clad switch on the distribution board available using No. 7/.064 and 7/.044 SWG insulated wires and accessories	One
4.	Do do in 1" braized conduit heavy gauge with flush 'T' junction boxes, bends, etc., embeded flush with the wall for 15 amp. 3 pin inter-locking wall plug protected with a pair of Home Office pattern 15 amp. fuses, completely mounted on a suitable T. W. Board with batten and rear boards enclosed in a sheet iron box fixed flush with the wall using No. 7/.044 and 7/.029 SWG insulated wires and accessories	5
5.	Earthing	Item

Part III—Lighting.

1.	Supplying, fixing and wiring Ivanhoe Trojan fittings, ceiling type with canopy 9" opal globe, etc., using necessary accessories	One
2.	Sildene fitting G. E. C. Cat. No. F. 10370 with chromium-plated complete with canopy holder, opal globe, etc.	5
3.	Brass pendants ⅝" complete with ceiling plate B. C. C. G. holder, all nickel-plated	5
4.	Shades, green and white opal	5
5.	Lamps, 100 watts, 220 volts, B. C. gas filled internally frosted	5
6.	Do do do 60 watts	6

M. HAYATH,
Superintendent.